




**MASTERFOAM INSULATION COMPANY
PRESSURIZED INSULATION
ESTIMATING GUIDE FOR BLOCK WALLS
2007**



The following table will allow your estimators to accurately calculate costing for foam injection on projects above 1000 sqft.. This is done by taking the total square feet of wall to be foamed and deducting any openings larger than 40 sqft. Leave grouted jams in and any grouted cells 54" on center or wider. Typically calculations are from the floor height (If block are capped off) to the bottom of the bond beam. MasterFoam has its own scissors lift (up to 25') so the floor should be poured, if it is not, a rough terrain scissors or boom lift will have to be rented and will be added to the cost. MasterFoam will travel 45 miles from our shop in Waukesha, any miles beyond the 45 miles, a charge of \$ 1.50 per mile will be added. If an over night is required, meals and lodging will be charged.


The following will apply for a 12" standard block wall

0 - 1000 sq ft	Time and material	
1001 - 1500 sq ft	\$.98 per square foot	\$.87 per block
1501 - 2000 sq ft	\$.88 per square foot	\$.77 per block
2001 - and above	\$.68 per square foot	\$.60 per block




The following will apply for a 8" standard block wall

0 - 1000 sq ft	Time and material	
1001 - 1500 sq ft	\$.87 per square foot	\$.78 per block
1501 - 2000 sq ft	\$.77 per square foot	\$.69 per block
2001 - and above	\$.55 per square foot	\$.48 per block



The following will apply for a 12" Enerblock wall

0 - 1000 sq ft	Time and material	
1001 - 1500 sq ft	\$ 1.12 per square foot	\$.99 per block
1501 - 2000 sq ft	\$1.02 per square foot	\$.90 per block
2001 - and above	\$.85 per square foot	\$.75 per block



Enerblock takes about 20% more foam but its design is superior for foaming and R-value and is highly recommended. Call for pricing on cavity wall situations.

Pricing good to Dec 31, 2007

Time & Material Rates

(All rates are charged from shop to job site and back)

Labor Cost per installer	\$46.00 per hour
Truck & Equipment costs	\$42.00 per hour
Resin & Foaming agent costs	\$2.30 per liter
Mortar (gray)	\$8.40 per bag
Lift Rental rough terrain scissors	\$150.00 Per day
Lift Rental (Boom)	\$240.00 Per day

If project requires an over night Meals and lodging will be charged.

Time & Material Profit table

Labor + Materials + Equipment + Lodging
Sub total
Overhead 18%
Profit 10%

FOR MORE INFORMATION

Contact:
JERRY PRAGER
at
Office: 1-262-542-0816

Visit our website: www.masterfoamwi.com